

ICAR-CENTRAL INSTITUTE FOR RESEARCH ON COTTON TECHNOLOGY
(INDIAN COUNCIL OF AGRICULTURAL RESEARCH),
ADENWALA ROAD, MATUNGA, MUMBAI-400019.
TEL NO.: 2412 7273/76, 2418 4274/75, 2415 7238
Email ID:-director.circot@icar.gov.in

Date: 13/03/2023

NOTICE INVITING E-TENDER No. 15 /2022-23

The Director, ICAR-Central Institute for Research on cotton Technology, (Indian Council of Agricultural Research), Adenwala Road, Matunga, Mumbai., invites online Percentage Rate based E-Tenders from approved and eligible contractors registered with Government organizations such as CPWD, state PWD, MES, Railway, P & T, Public undertakings, Nationalized banks etc., by e-tendering process for the following work:-

1	NIT No.	NIT. No.15/ E-Tenders-Works/ICAR-CIRCOT/2022-23
2	Name of Work	Providing and laying reinforced cement concrete pavement near front and side open space of Type-IV ICAR-CIRCOT staff quarters building at Mahim, Mumbai.
3	Estimated cost put to tender	Rs. 6,10,141/-
4	Tender fees (Rs.)	Rs. 1000/-
5	Earnest money deposit	Rs. 12,200/-
6	Period of Completion	60 (Sixty days)
7	Last Date & Time of submission of e-tender, and other documents as specified in the tender	Date:03-04-2023 Time: 15.00 hrs.
8	Time & Date of Technical bid opening of tender	Date: 05-04-2023 Time: 15.30 hrs.

1. The intending bidder must read the terms and conditions carefully. He should submit his bid if he considers himself eligible and he is in possession of all the documents required.
2. Information and instruction for bidders posted on website shall form part of bid document.
3. The bid document consisting of Plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents can be seen and downloaded from website www.circot.res.in or www.eprocure.gov.in free of cost.

4. Only on-line bids through NIC's e-procurement Portal (CPPP) i.e on www.eprocure.gov.in shall be accepted.

Sujatha Koshy
Ao

Estimate:

Name of Work: Providing and laying reinforced cement concrete pavement near front and side open space of Type-IV ICAR-CIRCOT staff quarters building at Mahim, Mumbai.

Sr. No	Item code as per DSR-21	Description of Item	Unit	Quantity	Rate(Rs)	Amount(Rs)
1.	2.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge: 2.1.1 All kinds of soil	Sq.mt	20.00	107.00	2140.00
2.	16.3.3	Supplying and stacking at site. 53 mm to 22.4 mm size stone aggregate	Cu.mt	20.00	1837.25	36745.00
3.	MR	Laying the stone aggregate of 53 mm to 22.4 mm	Cu.mt	20.00	350.00	7000.00
4.	5.1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 5.1.3 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cu.mt	22.00	7945.65	174804.30
5.	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. 5.22.1 Mild steel and Medium Tensile steel bars	Kg	3400.00	88.95	302430.00
6.	5.9	Cement plaster skirting up to 30 cm height, with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement. 18mm thick	Sq.mt	20.00	570.75	11415.00
7.	11.7	Cement concrete pavement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete.	Cu.mt	9.50	7958.65	75607.17
Total Amount=Rs 610141.47						
(Say) =Rs 6,10,141.00						


 SACHIN PATIL
 T.O. ENGG SECTION.